

# कार्यालय जोधपुर विकास प्राधिकरण, जोधपुर

क्रमांक :- 430

दिनांक : 14/10/2021

—:सीमित निविदा/विद्युत-1/01/2021-22::—

जोधपुर विकास प्राधिकरण, जोधपुर में निम्नलिखित कार्य हेतु संबंधित कार्य में कार्यरत पंजीकृत प्रतिष्ठानो/संवेदको/फर्मो से सीमित निविदा के माध्यम से बंद लिफाफे में दरे आमंत्रित की जाती है।

क्र. स.	कार्य का नाम	अनुमानित लागत (लाखों में)
1.	SITC of CCTV camera at JDA house for security purpose.	0.99 लाख

शर्तें :-

1. निविदादाता द्वारा प्रस्तुत की जाने वाली दरें समस्त करो सहित प्रस्तुत करनी होगी।
2. अन्य शर्तें एवं अनुसूची इत्यादि कार्यालय समय में प्राप्त की जा सकती है।
3. पेन कार्ड एवं जीएसटी की स्वप्रमाणित प्रति प्रस्ताव के साथ संलग्न करना अनिवार्य होगी।
4. निविदादाता दिनांक 20.10.2021 को दोपहर 2.00 बजे तक प्राप्त की जाकर उसी दिन दिनांक 20.10.2021 को सायं 5.00 बजे खोली जायेगी।



अधिशायी अभियंता (विद्युत-1)  
जोधपुर विकास प्राधिकरण,  
जोधपुर  
दिनांक :

क्रमांक :

प्रतिलिपि निम्नलिखित को सुचनार्थ प्रेषित है :-

- 1 एनालिस्ट कम प्रोग्रामर, जोधपुर विकास प्राधिकरण, जोधपुर को मय निविदा के प्रेषित कर लेख है कि कृपया संलग्न समिति निविदा [www.sppp.raj.nic.in](http://www.sppp.raj.nic.in) एवं जोधपुर विकास प्राधिकरण, जोधपुर की वेबसाईट पर तुरन्त प्रदर्शित करे।

अधिशायी अभियंता (विद्युत-1)  
जोधपुर विकास प्राधिकरण,  
जोधपुर

**OFFICE OF THE JODHPUR DEVELOPMENT AUTHORITY, JODHPUR**

Name of Work:-SITC of CCTV camera at JDA house for security purpose.

Name of Contractor:-.....

BSR ELECTRICAL 2021

**G-SCHEDULE**

S.No.	BSR Code	Item	Qty.	Unit	Rate	Amount
1	E201500	Supply, Installation, Testing and Commissioning of Wall mounted ISO 9001:2015 & 14001 or higher level certified company made Communication enclosure (Rack) of Minimum 500 MM Depth with made from CRCA & hot dip powder coated, front sturdy sheet steel frame folded from one piece and welded with minimum 5mm toughened glass door, Vertical Mounting: Rail 1.6 MM with U-Marking, with All round protective channel on the door aperture, lock integrated on front door, top and bottom cover with cable entry provision with gland plates, integrated side walls, 2 pair of 19" angles with wall mounting provision on wall. Accessories like: 1 No. of 19" 1U Horizontal Cable manager, 2 No. of 90 cfm 230V AC Fan with 1 mts long cable, mounting hardware, 1 No of 19" 1U, mountable socket strips with 6 nos of 5A universal sockets with 2 mts long power chord for supplying power to switches, fans etc along with earth continuity kit, indicator, moulded power supply cable. fixing on wall with fastener of suitable capacity etc as required complete in all respect. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work, refer Annexure "A" attached with this BSR. <b>6 Uwall mounted enclosure</b>	1	Nos.	6,505.00	6,505.00
2	E010411	S&F following sizes (dia.) of ISI marked MMS (IS:9537 P - III) virgin material PVC conduit as per PWD specification for electrical Works along with its accessories (IS: 3419) as required in recess including cutting the wall, covering conduit and making good the same as required. All relative and latest acceptance tests reports by any NABL accredited lab for the conduit shall be submitted before execution & All as per pre approved by Engineer in charge. For additional technical parameters of products/ work, refer Annexure "A" attached with this BSR. 20 mm	100	R Mtr.	30.00	3,000.00
3	E200100	Supply, Drawing and Testing of 4 pair, 23 AWG Solid Bare Copper wire insulated with PVC, UTP (Unshielded Twisted Pair), Category 6, Class E, 100 Ohm Impedance, Indoor Cable as per latest amendments of ANSI/TIA/EIA-568. The copper conductors should be balanced twisted in pairs, separated by a cross-member fluted pair divider & protected by PVC Jacket. Certified performance in a 4-conductor configuration upto 100 Mtrs channel requirements & transmission frequencies up to 250 Mhz in existing MS/PVC Conduits/casing capping including making connections to Information outlets and Patch Panels with jack & ferruling at both ends for identification with necessary tools for punching, stripping, crimping and testing etc as required complete in all respect. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work, refer Annexure "A" attached with this BSR.	100	Mtr.	30.00	3,000.00
<b>Total (G)</b>						<b>12505.00</b>

**H-SCHEDULE**

S.No.	BSR Code	Item	Qty.	Unit	Rate to be Quoted by Contractor	Amount
1	Non-BSR	SITC 8 Ch. Network Video Recorder: upto 8 channel IP camera input, Max 320 Mbps incoming bandwidth, smart H.265+/H.265/Samrt H.264+/H.264/ MJPEG, upto 12 MP resolution preview and playback, support 2 SATA HDDs upto 8 TB each, and, 2 USB (1 USB 2.0 and 1 usb 3.0), 1 HDMI/ 1 VGS simultaneous video output, support multi brand network cameras, ONVIF version 2.4 conformance product should be UL,FCC,CE,ROHS Make: CP Plus/Dahua/ Bosch/ Pelco/ Axis	1	Nos.		
2	Non-BSR	SITC 4MP Full HD WDR IR Bullet IP Camera: 1/3" 4MP CMOS Image Sensor, 4MP(2560x1440)@25/30 fps, support starlight technology, H.265+ and H.264+ dual stream coding, WDR(120db), 3D-DNR, ROI, HLC, BLC, Digital watermarking, rotation mode, 3.6 mm fixed lens(2.8mm optional), Built in IR range of 30 mtrs, IP67, Micro SD card, POE Mobile Software: iCMOB, gCMOB, CMS Software: KVMS Pro <b>Approved Make: (CP Plus, Panasonic, Axis, Bosch, Pelco)</b>	7	Nos.		
4	Non-BSR	<b>4TB HDD for Video Recorder (Approved Make: Seagate, Toshiba, WD)</b>	1	Nos.		
5	Non-BSR	<b>8 Port PoE Switch for site location 8x10/100/1000 POE + 2 Giga SFP uplink Port Make: CP/Dahua/ Dlink</b>	1	Nos.		
<b>Total (H)</b>						

नियम एवं शर्तें:-

- सभी प्रकार के कर्तव्य का युक्तान सचेदक को ही करना होगा।
- विद्युत संकेती दुर्घटना को शिथिलकारी देकरदार ही होगी।
- विद्युत संबंधित कार्य प्रशिक्षित सार्वजनिक मैन और वायर मैन द्वारा ही संचालित होगा।
- Bidder Should have a valid Authorization certificate of a OEM.

I/We hereby agree to do the above work @.....

Above/Below the G-Schedule.

GST No.

PAN No.

Signature of Contractor

अधिराशी अभियंता (जोन विद्युत-1)  
जोधपुर विकास प्राधिकरण  
जोधपुर