



# कार्यालय जोधपुर विकास प्राधिकरण, जोधपुर

रेल्वे अस्पताल के सामने रातानाडा, जोधपुर -342004  
वेब साईट-jodhpur.jda.org phone no. 0291-2656357

क्रमांक :- ६६/६/२०२०-२१/१५०५

दिनांक : १०/०२/२०२१

## संशोधित ई-निविदा सूचना संख्या: पूर्व-१६/२०२०-२१

कार्यालय जोधपुर विकास प्राधिकरण द्वारा जारी ई-निविदा सूचना संख्या: पूर्व-१६/२०२०-२१ क्रमांक १४३६ दिनांक ०५.०२.२०२१ आईटम संख्या ०१ वार्ड नं. ५७ सी रोड सारण नगर के आस-पास की गलियों में सडक निर्माण कार्य की ई-निविदा मे अपलोड जी शेड्यूल मे संवहन से त्रुटि रह गयी थी। अतः संलग्न जी शेड्यूल के अनुसार अपनी दरे BOQ मे प्रस्तुत की जावें।

कार्य का नाम :- वार्ड नं. ५७ सी रोड सारण नगर के आस-पास की गलियों में सडक निर्माण कार्य में अपरिहार्य कारणों से निम्नानुसार तिथियों में संशोधन

किया जाता है।

विवरण	आईटम संख्या	पूर्व दिनांक व समय	संशोधित दिनांक व समय
१. ऑनलाईन बिड फॉर्म की उपलब्धता डाउनलोड आरम्भ होने की दिनांक एवं समय	०१	दिनांक ०५.०२.२०२१ व समय ६:०० P.M.	दिनांक ०५.०२.२०२१ व समय ६:०० P.M.
२. ऑनलाईन बिड फॉर्म डाउनलोड समाप्त होने की दिनांक एवं समय	०१	दिनांक १६.०२.२०२१ व समय ६:०० P.M.	दिनांक २२.०२.२०२१ व समय ६:०० P.M.
३. ऑनलाईन बिड फॉर्म जमा कराने की प्रारम्भ होने की दिनांक एवं समय	०१	दिनांक ०५.०२.२०२१ व समय ६:०० P.M.	दिनांक ०५.०२.२०२१ व समय ६:०० P.M.
४. ऑनलाईन बिड फॉर्म जमा कराने की अन्तिम दिनांक एवं समय	०१	दिनांक १६.०२.२०२१ व समय ६:०० P.M.	दिनांक २२.०२.२०२१ व समय ६:०० P.M.
५. बिड शुल्क, एरोहर राशि Online SSO ID के माध्यम से जमा कराने की अन्तिम दिनांक व समय	०१	दिनांक १६.०२.२०२१ व समय ६:०० P.M.	दिनांक २२.०२.२०२१ व समय ६:०० P.M.
६. ऑनलाईन बिड खोलने की दिनांक व समय	०१	दिनांक १७.०२.२०२१ व समय ११:०० A.M.	दिनांक २३.०२.२०२१ व समय ११:०० A.M.

नोट:- अन्य शर्तें यथावत रहेगी।

अधिशायी अभियंता (जोन पूर्व)  
जोधपुर विकास प्राधिकरण,  
जोधपुर  
दिनांक :-

क्रमांक :-  
प्रतिलिपी

१. ए.सी.पी.एनआईसी जोधपुर विकास प्राधिकरण, जोधपुर।

//

अधिशायी अभियंता (जोन पूर्व)  
जोधपुर विकास प्राधिकरण,  
जोधपुर



## ODHPUR DEVELOPMENT AUTHORITY, JODHPUR

M/s. ....

D.D. No. .... Date ..... Rs. ....

BASED ON PWD Road BSR 2019

**G' SCHEDULE**

कार्य का नाम :- वार्ड नम्बर-57 सी रोड सारण नगर के आस-पास व अन्य गलियों में सड़क निर्माण कार्य।

S.No.	BSR	Item	Qty.	Unit	Rate In Rs.	Amount
1	2.4.10	Dismantling of flexible pavements and disposal of dismantled materials upto a lead of 1000 metres, stacking serviceable and unserviceable materials separately as per MORTH specification clause 202. By Mechanical Means : Bituminous courses	12.00	Cum.	220.00	2640.00
2	2.4.10	Dismantling of flexible pavements and disposal of dismantled materials upto a lead of 1000 metres, stacking serviceable and unserviceable materials separately as per MORTH specification clause 202. By Manual Means : Granular courses	23.00	Cum.	452.00	10396.00
3	14.2	Demolishing cement concrete including disposal of material within 50 meter lead : 1:3:6 or richer mix.	57.00	Cum.	742.00	42294.00
4	14.2	Demolishing cement concrete including disposal of material within 50 meter lead : 1:4:8 or leaner mix.	57.00	Cum.	455.00	25935.00
5	R-3.1.1.3	Earth work in excavation, including stacking/disposal of surplus material with all lifts and lead upto 495 metres, exclusive of compensation of earth [MoRTH specification : Clause 301 to 305]In ordinary Soil Mechanically by power shovel, including mechanical loading and carriage by tipper/dumper (6T capacity)	1006.00	Cum.	37.00	37222.00
6	G-5	Transportation of excavated earth with all km. lead	1155.00	Cum.	66.50	76807.50
7	5.2	Providing, laying, spreading and compacting stone aggregate of specific as per table 400-6 to Water Bound Macadam specification including spreading in uniform thickness, hand packing roll-ing with vibratory roller in stages to proper grade and camber, applying and brooming requisite type of screening and binding materials to fill-up the interstices of coarse aggregates watering (with water browser) and rolling making necessary earthen bund to protect edgcs, lighting, guarding, barricading and maintenance of diversion etc. [MoRTH specification : Clause 404] ( By manual means). Grading II, 53 mm to 22.4 mm, @ 0.91 cum per 10 Sqm for compacted thickness of 75 mm. (Crusher broken) Stone screening type 'B'	126.00	Cum.	1277.00	160902.00
8	RUIDP 4.6	Construction of subgrade and earthen shoulders with approved material obtained from borrow area with all lifts & leads, transporting to site, spreading, grading to required slope and compacted in layers not exceeding 200mm thickness at OMC, with vibratory roller of 80- 100 KN static weight or more to attain a density 97% maximum dry density to meet requirement of table No. 300-2 as per MoRT&H specification clause 305. (Lead taken upto 5 km)	1002.00	Cum.	185.00	185370.00
9	3.2	Providing and laying in position cement concrete including curing compaction etc. of specified grade excluding the cost of centering and shuttering All up to plinth level IS 456-2000. 1:3:6 (1Cement :3 Course Sand :6 Graded stone aggregate 20 mm nominal size	906.00	Cum.	3127.00	2833062.00

S.No.	BSR	Item	Qty.	Unit	Rate In Rs.	Amount
10	3.2	Providing and laying in position cement concrete including curing compaction etc. of specified grade excluding the cost of centering and shuttering All up to plinth level IS 456-2000: 1:1.5:3 (1Cement :1.5 Course Sand :3 Graded stone aggregate 20 mm nominal size	2152.00	Cum	3979.00	8562808.00
11	RUIDP 17.70	Raising precast circular manhole cover and frame by taking out existing precast frame and cover, providing and fixing precast SFRC circular spacer of height 100/125/150mm, re-fixing existing manhole cover frame and cover with cement sand mortar (1:3), including making good the damage, complete as directed by Engineer.	89.00	0.00	1510.00	134390.00
<b>Total</b>						<b>12071826.50</b>

**नियम एवं शर्त :-**

1. बिना बिड़ सुरक्षा राशि एवं सशर्त बिड़ मान्य नहीं होगी।
2. बिड़ सुरक्षा राशि online SSOID के माध्यम से जमा कराने पर ही बिड़ विक्रय की जायेगी/मान्य होगी।
3. एक या एक से अधिक बिड़ पूर्णतः बिना कारण बताये स्वीकार/अस्वीकार करने का अधोहस्ताक्षरकर्ता को अधिकार
4. बिड़ विक्रय/प्राप्ति के अवकाश होने पर बिड़ स्वतः आगामी कार्य दिवस को प्राप्ति/विक्रय कर खोली जायेगी।
5. बिड़ से सम्बन्धित अन्य आवश्यक शर्तें कार्यालय समय में देखी जा सकती हैं।
6. बिड़ सुरक्षा राशि सचिव, जोधपुर विकास प्राधिकरण के नाम से online SSOID से देय होगी।  
होगा।
8. 'G' Schedule पर केवल % Above/Below दरे ही स्वीकार्य होगी। शेड्यूल-एच में आईटम दरे स्वीकार्य होगी।
9. कार्य की गुणवत्ता जांच बिड़र द्वारा निर्धारित माप दण्डों के अनुरूप स्वयं के खर्च पर करानी होगी।
10. बिड़र को GSTIN Number प्रमाण-पत्र अपलोड करना आवश्यक है।
11. उक्त कार्यों में दोष निवारण (Defect Liability Period) अर्थात् पांच वर्ष की रहेगी।
12. बिड़ के साथ अनुलग्न परिशिष्ट A से D बिन्दु के मारा हैं, जिराकी पूर्ति अनिवार्य है।

  
 EXECUTIVE ENGINEER (Zone-East)  
 JODHPUR DEVELOPMENT AUTHORITY  
 JODHPUR

I/We hereby agree to do the above work @ \_\_\_\_\_  
 Above/below the 'G' Schedule

GST No.....  
 PAN No.....

**Signature of contractor**